

1060246

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 185-21,973.0000

SW SE SE, SEC. 3, T 21 S, R 14 W/E

330 feet from N/S section line

990 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8408

Lease Name Nina Davis Well # 2

Operator: Duane Exploration Limited

County Stafford

Name & Address P. O. Box 497

Well Total Depth 3751 121.91 feet

Andover, KS 67002

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 419

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor H-30 Drilling License Number 5107

Address 251 North Water, Wichita, KS 67202

Company to plug at: Hour: 2:00 pm Day: 5 Month: June Year: 19 84

Plugging proposal received from Rick Davis

(company name) H-30 (phone) 316-792-2260

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 3750' with 50 sx cement

2nd plug at 780' with 50 sx cement

3rd plug at 450' with 50 sx cement  
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Paul A. Luthie (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 4:15 pm Day: 5 Month: June Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 3750' with 50 sx cement, 2nd plug at 780' with 50 sx

cement, 3rd plug at 450' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

15 sx cement.

RECEIVED STATE CORPORATION COMMISSION

JUN 07 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun

(if additional description is necessary, use BACK of this report)  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

(copy to be kept) observe this plugging.

DATE 6-15-84

Signed Paul A. Luthie (TECHNICIAN)

INV. NO. 2020

6-5