

To: 052201
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

12-1

API NUMBER 15-Drilled 9/65
NE SW SW, SEC. 1, T 21 S, R 14 W EX
990 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767
Operator: Ritchie Exploration, Inc.
Name & Address P.O. Box 783188
Wichita, KS 67278-3188

Lease Name Morrison P Well # 8
County Stafford 117.94
Well Total Depth 3629 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 283

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529

Address P.O. Box 467, Chase, KS 67524

Company to plug at: Hour: 3:30 p.m. Day: 1 Month: 12 Year: 19 97

Plugging proposal received from Mike Kelso

(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

Work: 5 1/2" at 3628' w/175 sx cement, PBSD 3602', Perfs at 3351-3475'

1st plug sand back to 3300' and dump .5 sx cement on top of sand through bailer,

2nd plug at 900' with 10 sx gel and 50 sx cement,

3rd plug circulate cement to surface from 400-0'

124-97

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 6:30 p.m. Day: 1 Month: 12 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 3300' and dumped 5 sx cement on top of sand through bailer,

Spotted plugs down 5 1/2" casing:

2nd plug at 900' with 10 sx gel and 50' sx cement,

3rd plug at 400' with 145 sx cement, circulated to surface,

4th plug pulled pipe and topped off hole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1800' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE DEC 17 1997 observe this plugging.

INV. NO. 49699

Signed Richard W. Lacey
(TECHNICIAN)