

15.195.10758.0001

052198

11-26

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- Drilled 5/59  
SW NE SW, SEC. 1, T 21 S, R 14 W/2  
1650 feet from S section line  
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767  
Operator: Ritchie Exploration, Inc.  
Name:  
Address: P.O. Box 783188  
Wichita, KS 67278-3188

Lease Name Morrison P Well # 5  
County Stafford 118-11  
Well Total Depth 3634 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 280

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529  
Address P.O. Box 467, Chase, KS 67524

Company to plug at: Hour: 11 a.m. Day: 26 Month: 11 Year: 19 97

Plugging proposal received from Mike Kelso

(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

Work: 5 1/2" at 3631' w/175 sx cement, Perfs at 3456-94, 3631-34'  
1st plug sand back to 3394' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.  
hulls and 125 sx cement.

12-4-97  
REC'D  
PLUGGING SECTION  
STATE CORPORATION COMMISSION  
WICHITA, KANSAS

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 12 p.m. Day: 26 Month: 11 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 3394' and dumped 5 sx cement on top of sand through bailer,  
2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.  
hulls and 125 sx cement.

Maximum pressure 500 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1800' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

I (did / XXXXXX) observe this plugging.

DATE DEC 10 1997

INV. NO. 49624

Signed Richard M. Lacey (TECHNICIAN)