

15.185.00476.0000

To: 1052202
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- Drilled 11/58
NW SW SW, SEC. 1, T 21 S, R 14 WEX
990 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 4767

Lease Name Morrison P Well # 1

Operator: Ritchie Exploration, Inc.
Name:
Address: P.O. Box 783188
Wichita, KS 67278-3188

County Stafford 118.20
Well Total Depth 3637 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 275

Abandoned Oil Well Gas Well _____ Input Well _____ SKD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529

Address P.O. Box 467, Chase, KS 67524

Company to plug at: Hour: 12:30 p.m. Day: 1 Month: 12 Year: 19 97

Plugging proposal received from Mike Kelso

(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

was: 5 1/2" at 3633' w/175 sx cement, PBSD 3615', Perfs at 3391-3504'

1st plug sand back to 3340' and dump 5 sx cement on top of sand through bailer,

2nd plug at 900' with 10 sx gel and 50 sx cement,

3rd plug circulate cement from 400-0'.

12-4-97

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 1 1997

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3 p.m. Day: 1 Month: 12 Year: 1997

ACTUAL PLUGGING REPORT 1st plug sanded back to 3340' and dumped 5 sx cement on top of sand through bailer,

Spotted plugs through 5 1/2" casing:

2nd plug at 900' with 10 sx gel and 50 sx cement,

3rd plug at 400' to surface with 150 sx cement, circulated,

4th plug pulled pipe and topped off hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1800' of 5 1/2" casing.

INVOICED

(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

DATE DEC 17 1997

Signed Richard M. Lacey (TECHNICIAN)

INV. NO. 49698