

To: 1 052039
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- Drilled 11/64 15-85-30019.0000

NE NW NE, SEC. 1, T 21 S, R 14 W/EX

4950 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 30517

Lease Name Morrison Well # 1

Operator: Turnco Drilling, Inc.

County Stafford

Name:

Address 3900 Broadway

Well Total Depth 3566 115.89 feet

Great Bend, KS 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 285

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage Inc. License Number 31529

Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 9 a.m. Day: 7 Month: 5 Year: 19 96

Plugging proposal received from Mike Kelso

(company name) Mike's Testing & Salvage Inc. (phone) 316-938-2943

work: 5 1/2" at 3560' w/150 sx cement, PBTD 3467', Perfs at 3455-58, 3439-41, 3417-25, 3356-62'

1st plug sand back to 3300' and dump 5 sx cement on top of sand through bailer,

2nd plug at 840' with 50 sx cement,

3rd plug at 315' with 50 sx cement,

4th plug at 40' with 10' sx cement.

RECEIVED
STATE CORPORATION COMMISSION
MAY 21 1996

Plugging Proposal Received by Steve Pfeiffer (TECHNICIAN) WICHITA, KS

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12 p.m. Day: 7 Month: 5 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 3300' and dumped 5 sx cement on top of sand through bailer,

2nd plug shot at 350'-couldn't pull. Pumped 50 sx cement and displaced,

3rd plug shot at 300'-couldn't pull. Pumped 50 sx cement down 5 1/2".

4th plug pumped 10 sx cement down 8 5/8".

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED
I (date) observed this plugging.

Signed Richard W. Lacy (TECHNICIAN)

DATE

INV. NO. 45691