

1 050800

API NUMBER 15- 185-21,112.0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE SW NW, SEC. 1, T 21 S, R 14
3630 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5430

Lease Name Morrison Trust Well # 2

Operator: Energy Three, Inc.
Name & Address: P. O. Box 1505
Great Bend, KS 67530

County: Stafford 117.62
Well Total Depth 3619 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 254

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 2:15 pm Day: 22 Month: April Year: 19 86

Plugging proposal received from Mark McCabe

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 3615' Perfs at 3578-84' & Open Hole

1st plug sand back to 3530' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 70 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 100 sx cement.

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:15 pm Day: 22 Month: April Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 3530' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 70 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 100 sx cement

Maximum pressure 400 psi and shut in 50 psi

Remarks: Recovered 2035' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.
(if additional description is necessary, use BACK of this form.)

INVOICED
(if possible) observe this plugging.

DATE APR 29 1986

Signed Richard W. Lacey (TECHNICIAN)

INV. NO. 13570

STATE CORPORATION COMMISSION
APR 28 1986
CONSERVATION DIVISION
Wichita, Kansas