

12-30-87

1050981

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-22,732

SW SW NW, SEC. 23, 'T 21 S, R 13 W/E

2970 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4104

Lease Name Schmalian Well # 1

Operator: Blackhawk Energy Corporation

County Stafford 119.80

Name & Address P.O. Box 1910

Well Total Depth 3686 feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 303

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11 a.m. Day: 30 Month: 12 Year: 19 87

Plugging proposal received from Clay Duntz

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 3685' Perfs at 3318-3529'

1st plug sand back to 3270' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:15 p Day: 30 Month: 12 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 3270' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"

wiper plug and pumped 100 sx cement.

Maximum pressure 400 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2451' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
observe this plugging.

DATE 1-11-88

Signed Richard W Lacey
(TECHNICIAN)

INV. NO. 19476

JAN 04 1988
1-4-88
Wichita Kansas