

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-01855-00-00
Spot: CNENENE Sec/Twnshp/Rge: 5-21S-14W
4950 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: DORFSHAFFER Well Number: 1
County: STAFFORD Total Vertical Depth: 3544 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

Conductor Pipe: Size feet: 8 1/2
Surface Casing: Size 8.625 feet: 830 WITH 575 SX CMT
Production: Size 5.5 feet: 3543 WITH 90 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/11/2001 3:00 PM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3200' & 5 SX CMT. 1ST PLUG AT 860' WITH 10 SX GEL - 50 SX CMT. 2ND PLUG AT 400' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT

Plugging Proposal Received By: RICHARD LACEY
Date/Time Plugging Completed: 12/11/2001 4:37 PM

Witness Type: Plugging Operations 100% Witnessed (Complete)
KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 3464'. PERFS AT 3281-86, 3308-12, 3350-54, 3399-3403, 3416-20, 3428-31, 3443-46, 3448-54'. SAND TO 3200' & 5 SX CMT WITH DUMP BAILER. PUMPED PLUGS THROUGH CASING. 1ST PLUG AT 860' WITH 10 SX GEL - 50 SX CMT. 2ND PLUG AT 400' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2000' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed Richard M. Lacey
(TECHNICIAN)

RECEIVED INVOICED DEC 28 2001

DEC 31 2001 DATE 01-02-02

WICHITA W.V. NO. 200 206 1110

Form 6823