

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-10774-00-01  
Spot: NWNENE Sec/Twnshp/Rge: 5-21S-14W  
4950 feet from S Section Line, 990 feet from E Section Line  
Lease/Unit Name: DORSHAFFER OWWO Well Number: 2  
County: STAFFORD Total Vertical Depth: 3561 feet

Operator License No.: 5363  
Op Name: BEREXCO, INC.  
Address: PO BOX 20380  
WICHITA, KS 67208

Conductor Pipe: Size feet: 115.73  
Surface Casing: Size 8.625 feet: 835 WITH 1000 SX CMT  
Production: Size 5.5 feet: 3553 WITH 125 SX CMT  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/13/2001 8:30 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3230' & 5 SX CMT. 1ST PLUG AT 860' WITH 10 SX GEL - 50 SX CMT. 2ND PLUG AT 400' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 12/13/2001 2:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 3522'. PERFS AT 3298-3310, 3323-30, 3346-50, 3364-70, 3380-83'. SANDED TO 3230' & 5 SX CMT WITH DUMP BAILER. PUMPED PLUGS THROUGH CASING. 1ST PLUG AT 860' WITH 10 SX GEL - 50 SX CMT. WELL MAKING GAS. PUMPED ANOTHER 50 SX CMT TO KILL GAS. QUIT MAKING GAS AFTER CEMENTING. 2ND PLUG AT 400' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2000' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED  
KANSAS CORPORATION COMMISSION

Signed Richard W. Lacey  
(TECHNICIAN)

JAN 07 2002

CONSERVATION DIVISION

DEC 28 2001

INVOICED

DATE 01-08-02

INV. NO. 2002061216