

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-19007-00-00  
Spot: NENE Sec/Twnshp/Rge: 5-21S-14W  
4440 feet from S Section Line, 660 feet from E Section Line  
Lease/Unit Name: DORFSHAFFER Well Number: 4  
County: STAFFORD Total Vertical Depth: 3560 feet

Operator License No.: 5363  
Op Name: BEREXCO, INC.  
Address: PO BOX 20380  
WICHITA, KS 67208

Conductor Pipe: Size feet: 8 1/5.70  
Surface Casing: Size 8.625 feet: 844 WITH 450 SX CMT  
Production: Size 5.5 feet: 3558 WITH 125 SX CMT  
Liner: Size feet:

Well Type: SWD UIC Docket No: D18299.0 Date/Time to Plug: 12/17/2001 11:30 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3850' & 5 SX CMT. 1ST PLUG AT 860' WITH 10 SX GEL - 50 SX CMT. 2ND PLUG AT 400' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY  
Date/Time Plugging Completed: 12/17/2001 1:15 PM

WitnessType: Plugging Operations 100% Witnessed (Complete)  
KCC Agent: RICHARD LACEY

Actual Plugging Report:

PERFS AT 3414-17, 3442-46'. OPEN HOLE 3558-3731'. SANDED TO 3850' & 5 SX CMT WITH DUMP BAILER. 1ST PLUG AT 860' WITH 10 SX GEL - 50 SX CMT. 2ND PLUG AT 400' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Remarks: USED 60/740 POZMIX 6% GEL BY ALLIED. RECOVERED 1920' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed Richard W. Lacey  
(TECHNICIAN)

RECEIVED

INVOICED

DEC 26 2001

DEC 31 2001

DATE 01-02-02

WICHITA

NO. 2002061110

Form CP-117