

1 080352

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Completed 6-17-59  
NW NW SE, SEC. 5, T 21 S, R 14 W/E  
2310 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6939

Lease Name Boyd Well # 1

Operator: Chapman Exploration, Inc.  
Name & Address 404 Cities Service Building  
Tulsa, OK 74119

County Stafford 117.49

Well Total Depth 3615 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 251 ✓

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sun Cementers License Number \_\_\_\_\_

Address Box 169, Great Bend, KS 67530

Company to plug at: Hour: 10:00 am Day: 25 Month: March Year: 19 85 ✓

Plugging proposal received from Fred Soverign

(company name) Chapman (phone) 918-582-2247

were: 5 1/2" at 3613' Perfs at 3520-24

1st plug squeeze 5 1/2" with 2 sx hulls, 50 sx cement, 20 sx gel, 100 sx cement

2nd plug pump 2 1/2 sx hulls and 150 sx cement down 8 5/8"

Plugging Proposal Received by J. A. [Signature]  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:20 am Day: 25 Month: March Year: 19 85

ACTUAL PLUGGING REPORT 1st plug squeezed 5 1/2" with 2 sx hulls, 50 sx cement, 20 sx gel and 100 sx cement - Maximum pressure 200 psi and shut in 0

2nd plug pumped 2 1/2 sx hulls and 150 sx cement down 8 5/8" - Maximum pressure 300 psi and shut in 150 psi

RECEIVED  
STATE CORPORATION COMMISSION

APR 04 1985

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun No recovery  
(if additional description is necessary, use BACK of this form.)  
Wichita, Kansas

INVOICED observe this plugging.

DATE 4-8-85

Signed J. A. [Signature]  
(TECHNICIAN)

INV. NO. 7517  
3-25