

152376

TO: STATE CORPORATION COMMISSION

API NUMBER 15-185-10,836-0000  
NW NE NW SEC. 34, T 21 S, R 14 W

CONSERVATION DIVISION - PLUGGING SECTION 4950 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 3630 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME MCGINTY WELL # 2

TECHNICIAN'S PLUGGING REPORT

3/7

COUNTY STAFFORD 123.01

OPERATOR LICENSE # 4058

WELL TOTAL DEPTH 3785 FEET

OPERATOR: AMERICAN WARRIOR

PRODUCTION CSG: SIZE 5 1/2" @ 3783' WITH SX

NAME AND PO BOX 399

SURFACE CASING: SIZE 8 5/8" @ 249' WITH SX

ADDRESS GARDEN CITY, KS 67846

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL ~~D-19, 987~~ D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR D S & W LICENSE NUMBER 6901

ADDRESS 403 FRONT STREET CLAFLIN, KS 67525

COMPANY TO PLUG AT: HOUR: 10:30 AM DAY: 07 MONTH: 03 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM BRIAN

(COMPANY NAME) D S & W (PHONE) 316-587-3361

WERE: PERFS AT 3564-3569

SAND TO 3500' AND 5 SX CEMENT. 1ST PLUG AT 800' WITH 10 SX GEL - 50 SX CEMENT.

2ND PLUG AT 280' WITH 40 SX CEMENT. 3RD PLUG AT 40' WITH 20 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 12:28 PM DAY: 07 MONTH: 03 YEAR: 2000

ACTUAL PLUGGING REPORT

SAND TO 3500' AND 5 SX CEMENT. 1ST PLUG AT 800' WITH 10 SX GEL - 50 SX CEMENT.

2ND PLUG AT 280' WITH 40 SX CEMENT. 3RD PLUG AT 40' WITH 20 SX CEMENT.

RECEIVED

STATE CORPORATION COMMISSION

MAR 13 2000

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1800' OF 5 1/2" CASING  
Wichita, Kansas

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

INVOICED

DATE 3/13/00

SIGNED Richard W. Lacey  
(TECHNICIAN)

FORM CP-2/3

INV. NO. 061417