

1 030816

JUN 4 1987

15.185.13248.0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drill completion 5/26/62
SE SE SW, SEC. 34, T 21 S, R 14 W/E
330 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4519
Operator: Chevron U.S.A. Inc.
Name &
Address P.O. Box 12116
Oklahoma City, OK 73157

Lease Name Schartz "C" Well # 1
County Stafford 123.18
Well Total Depth 3790 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 245

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Services License Number NA

Address 6th Floor, Colorado-Derby Bldg., Wichita, KS 67202

Company to plug at: Hour: 8:30 a.m. Day: 14 Month: 6 Year: 19 87

Plugging proposal received from Dink Klutts

(company name) Chevron U.S.A. Inc. (phone) 316-265-3169

were: 5 1/2" at 3786' PBTD 3684 & 3500' Perfs at 3546-50, 3584-90, 3606-10, 3654-57, 3671-74, 3690-96, 3700-04, 3636-44'

1st plug cement retainer at 3500' with 1 sx hulls and 50 sx cement,

2nd plug test 500 fill with perf 850' and pump full.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 2 p.m. Day: 14 Month: 6 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug set CIBP at 3684' with 5 sx cement,

2nd plug set CIBP at 3500' with 5 sx cement on top,

3rd plug set CIBP at 900' with 5 sx cement,

4th plug perforate at 850' - run cement retainer at 800', pump 300 sx Class H cement,

5th plug pump 50 sx cement at 500',

6th plug fill 8 5/8" & 5 1/2" from top with 40 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JUN 17 1987

Remarks: Used Class H cement by Halliburton. No recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED
(If additional description is necessary, use BACK of this form.) Observe this plugging.

Signed Steve Sherront
(TECHNICIAN)

DATE 6-18-87

INV. NO. 17269
6-14