

To: 1 061088
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

3-30-88
API NUMBER 15-097-20,588 Docket #E-23,572

C E/2 NW NW, SEC. 11, T 28 S, R 16 W/E
4620 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4548
Operator: ONEOK Exploration
Name & Address: RR 1, Box 122A
El Reno, OK 73036-9702

Lease Name Rinkel A Well # 1-11
County Kiowa 151.94
Well Total Depth 4675 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 362

Abandoned Oil Well _____ Gas Well _____ Input Well SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 4:15 p.m. Day: 30 Month: 3 Year: 19 88

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 4664' PBSD 4645' Perfs at 4672-75' Elevation 2118' GL

1st plug sand back to 4625' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 120 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5 p.m. Day: 30 Month: 3 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4625' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, 8 5/8" wiper plug and pumped 120 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

Maximum pressure 800 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2450' of 5 1/2" casing
(If additional description is necessary, use BACK of this form.)

APR - 1 1988
CONSERVATION DIVISION
Wichita, Kansas

INVOICED observe this plugging.

Signed Paul A. Luthi (TECHNICIAN)

DATE 4-5-88

INV. NO. 20293