

3-30-88

1 061089

API NUMBER 15-097-20,598-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C SW NW, SEC. 11, T 28 S, R 16 W/4E

3300 feet from S section line

4620 feet from E section line

Lease Name Rinkel "B" Well # 1-11

County Kiowa 153.17

Well Total Depth 4713 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 376

TECHNICIAN'S PLUGGING REPORT

Operator License # 4548

Operator: ONEOK Exploration

Name &

Address RR 1, Box 122A

El Reno, OK 73036-9702

Abandoned Oil Well  Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 11:30 a.m. Day: 30 Month: 3 Year: 19 88

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4712' PBSD 4683' Perfs at 4682-85' Elevation 2117' GL

1st plug sand back to 4630' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 120 sx cement.

Plugging Proposal Received by Steve Durrant

(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:45 p.m. Day: 30 Month: 3 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4630' and dumped 4 sx cement on top

sand through bailer,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released

8 5/8" wiper plug and pumped 120 sx cement.

Maximum pressure 750'psi and shut in 500 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2495' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

and (KX) observe this plugging.

INVOICED

DATE 4-5-88

Signed Paul A. Lutte (TECHNICIAN)

WV. NO. 20296

RECEIVED STATE CORPORATION COMMISSION

APR - 1 1988

CONSERVATION DIVISION Wichita, Kansas

Handwritten initials