

1 040369

11-30

API NUMBER 15-097-20,618 - 00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW NW NE, SEC. 11, T 28 S, R 16 W/E
4950 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5317

Lease Name Davis-Day Well # 1

Operator: Continental Energy

County Kiowa 154.05

Name & Address P.O. Box 918

Well Total Depth 4740 feet

Garden City, KS 67846

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 425

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10:15 a.m. Day: 30 Month: 11 Year: 19 89

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 4 1/2" at 4739' Perfs at 4672-80'

1st plug sand to 50' above the perfs with 4 sx cement on top,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

12-5-89 DEC 5 1989

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:45 a.m. Day: 30 Month: 11 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4620' and dumped 4 sx cement on top of sand bridge with bailer.

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 800 psi and shut in 650 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 3004' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

(City/State) observe this plugging.

DATE DEC 08 1989

Signed Steve Pfeifer
(TECHNICIAN)

INV. NO. 26706