

To: 1 040616 1-31
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-097-20,659-0000 166
SW SW NW, SEC. 11, T. 28 S, R. 16 W&E

TECHNICIAN'S PLUGGING REPORT

Operator License # 3399
Operator: Farrar Pump & Supply Co. Inc.
Name & Address P.O. Box 209
Medicine Lodge, KS 67104

2970 feet from S section line
4950 feet from E section line
Lease Name Rinkel "B" Well # 3-11
County Kiowa 153.59
Well Total Depth 4726 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 382

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers License Number 4635
Address P.O. Box 251, Great Bend, KS 67530

Company to plug at: Hour: 9:15 a.m. Day: 31 Month: 1 Year: 19 92

Plugging proposal received from Gary Burke
(company name) Great Bend Casing Pullers (phone) 316-793-9711

were: 5 1/2" at 4724' w/200 sx cement, PBTD 4711', Perfs at 4568-78, 3486-90'
1st plug sand back to 3430' and dump 5 sx cement on top of sand through bailer,
2nd plug pump down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 10:30 a.m. Day: 31 Month: 1 Year: 19 92.

ACTUAL PLUGGING REPORT 1st plug sanded back to 3400' and dumped 5 sx cement on top of sand
bridge through bailer.
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.
Maximum pressure 500 psi and shut in 350 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2603' of 5" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 2-11-92
INV. NO. 34499

Signed Steve Pfeifer
(TECHNICIAN)

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
WICHITA, KANSAS
FEB 04 1992