

3-30-88

1 061090

API NUMBER 15-097-20,661-000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE SE NW, SEC. 11, T 28 S, R 16 W

3630 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4548

Lease Name Rinkel "B" Well # 2-11

Operator: ONEOK Exploration
Name & Address RR 1, Box 122A

County Kiowa 155.6/

Well Total Depth 4788 feet

El Reno, OK 73036-9702

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 378

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 3 p.m. Day: 30 Month: 3 Year: 1988

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 816-886-5665

were: 4 1/2" at 4787' PBD 4758' Perfs at 4646-50, 4670-78'

1st plug sand back to 4596' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 120 sx cement.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4 p.m. Day: 30 Month: 3 Year: 1988

ACTUAL PLUGGING REPORT 1st plug sanded back to 4596' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 120 sx cement.

Maximum pressure 400 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2817' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED (did not observe this plugging.)

DATE 4-5-88

Signed Paul A. Suttie (TECHNICIAN)

INV. NO. 20295

RECEIVED STATE CORPORATION COMMISSION APR 1 1988 4-1-88 CONSERVATION DIVISION Wichita, Kansas