

1 040367

11-30

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-097-20,666-00-00

SW SE NE, SEC. 11, T 28 S, R 16 W/E
2970 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5317

Lease Name Davis-Day Well # 3

Operator: Continental Energy

County Kiowa 155.03

Name & Address Box 918

Well Total Depth 4770 feet

Garden City, KS 67846

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 410

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 12:30 p.m. Day: 30 Month: 11 Year: 19 89

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 4 1/2" at 4754' Perfs at 4655-57'

1st plug sand back to 4608' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 125 sx cement.

12-5-89

STATE CORPORATION COMMISSION
WICHITA, KANSAS
DEC 5 1989

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1 p.m. Day: 30 Month: 11 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4600' and dumped 4 sx cement on top of sand bridge with bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and 125 sx cement.

Maximum pressure 700 psi and shut in 500 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2612' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

(to be observed) observe this plugging.

DEC 08 1989

Signed Stephen J. Pfeifer
(TECHNICIAN)

SPJ

DATE _____

INV. NO. 26704