

To: 1 040308
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

8-8

API NUMBER 15-097-20,670-0002
NW NW SW, SEC. 11, T 28 S, R 16 W/E
2310 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5171
Operator: TXO Production Corporation
Name & Address 1660 Lincoln Street, Suite 1800
Denver, CO 80264

Lease Name Ross "F" Well # 1
County Kiowa 156.55
Well Total Depth 4817 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 429

Abandoned Oil Well Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105
Address 107 West Fowler, Medicine Lodge, KS 67104

Company to plug at: Hour: 1:15 p.m. Day: 8 Month: 8 Year: 19 89

Plugging proposal received from Elmo Morgenstern
(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4816' Perfs at 4726-30, 4681-89, 4655-57, 3470-73', CIBP at 4606' Cement Retainer at 3500'
1st plug sand back to 3420' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release wiper plug and pump 120 sx cement.

Plugging Proposal Received by Mike Wilson
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:15 p.m. Day: 8 Month: 8 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back from 3500-3420' and dumped 4 sx cement on top of sand bridge with bailer,

2nd plug pumped down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 120 sx cement.

Maximum pressure 700 psi and shut in 300 psi.

RECEIVED
STATE CORPORATION COMMISSION
AUG 15 1989
CONSERVATION DIVISION
Wichita Kansas

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2350' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
To observe this plugging.

DATE 8-18-89

Signed Stephen J. Pfeifer
(TECHNICIAN)

REV. NO. 25682
8-8