

1 060956

MAY 1 1 1987

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 097-20,863 - 0900

NE NE SE, SEC. 11, T 28 S, R 16 (W/E)

2310 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Ross "F" Well # 3

Operator: TXO Production Corporation

County Kiowa 156.59

Name & Address 155 North Market, Suite 1000

Well Total Depth 4818 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 415

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Hays Well Service License Number 5429

Address P.O. Box 108, Attica, KS

Company to plug at: Hour: 10 a.m. Day: 11 Month: 5 Year: 19 87

Plugging proposal received from Vernon Schraut

(company name) TXO Production Corporation (phone) 316-269-7600

were: 4 1/2" at 4817' Perfs at 4655-60; CIBP @ 4610; 3546-48; 3484-89'

1st plug sand back to 3340' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11 a.m. Day: 11 Month: 5 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 3340' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 700 psi and shut in 350 psi. Used 60/40 Pozmix 6% gel by B.J. Titan.

Remarks: Recovered 2427' of 4 1/2" casing. (If additional description is necessary, use BACK of STATE CORPORATION COMMISSION

INVOICED (If additional description is necessary, use BACK of STATE CORPORATION COMMISSION) observe this plugging.

DATE 5-15-87

Signed Paul A. Luthi (TECHNICIAN)

INV. NO. 16921

RECEIVED MAY 17 1987 CONSERVATION DIVISION Wichita, Kansas FORM CP-2/3 Rev. 01-84