

1 090297

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-097-20,877-000
SE, SEC. 11, T 28 S, R 16 W/X
1190 feet from N/S section line
330 feet from N/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Grossman "A" Well # 1

Operator: TXO Production Corp.

County Kiowa 155.87

Name & Address 200 W. Douglas, Suite 300

Well Total Depth 4796 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 420 ✓

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 1:45 pm Day: 5 Month: March Year: 19 85

Plugging proposal received from Bill Folls

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" set at 4757' PBTD 4728' Perfs at 4675-79, 4692-4700, 4684-88 4654-58
4654-60

1st plug sand back to 4600' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls

release 8 5/8" rubber plug and pump 120 sx cement

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:00 pm Day: 5 Month: March Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4600' and dumped 4 sx cement on top of
sand through bailer, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement,
10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped an additional 120 sx
cement.

RECEIVED
STATE CORPORATION COMMISSION

MAR 11 1985

Maximum pressure 800 psi and shut in 450 psi CONSERVATION DIVISION
Wichita, Kansas

Remarks: Recovered 2500' 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc b6 Sun # 206674
(if additional description is necessary, use BACK of this form.)

INVOICED (if desired, please observe this plugging.)

Signed Robert Barntson
(TECHNICIAN)

DATE 3-12-85

INV. NO. 7329

3-5