

1 060825

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-20,676.0000

NE SW SE, SEC. 30, T 21 S, R 13 W/E XX

990 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4678

Lease Name Keenan Well # 1

Operator: LASMO Energy Corp.

County Stafford

Name & Address (Southern States)

Well Total Depth 3743 121.65 feet

2700 E. 51st Street, #480

Conductor Pipe: Size feet 3714

Tulsa, OK 74105

Surface Casing: Size 8 5/8 feet 308

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9:30 am Day: 6 Month: March Year: 19 86

Plugging proposal received from Clay Duntz

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 3739' Perfs at 3561-64'; 3680-88'; 3545-48'; 3524-27'; 3507-11'

1st plug sand back to 3450' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 130 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10:30 am Day: 6 Month: March Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 3450' and dumped 5 sx cement on top of

sand through bailer, 2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement,

10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 130 sx cement.

Remarks: Recovered 2600' 5 1/2" casing. Cemented by Allied.
(If additional description is necessary, use BACK of this form.)

I (did not) observe this plugging.

INVOICED

STATE CORPORATION COMMISSION

Paul A. Luthi (TECHNICIAN)

DATE MAR 10 1986

MAR 10 1986

INV NO 12880

CONSERVATION DIVISION

FORM CP-2/3 Rev. 01-84