

2-0706012

KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2125
Wichita, KS 67202

4-9

API NUMBER: 15-155-21,340-0000

C NE NW SEC 35, T 23 S, R 9W

OPERATOR LICENSE # 30080

4620 FEET FROM S SECTION LINE

OPERATOR: Honey Oil Co., Inc.

3300 FEET FROM E SECTION LINE

NAME & 401 E. Douglas, #505

LEASE NAME: Tina WELL # 1

ADDRESS: Wichita, KS 67202

COUNTY: Reno

WELL TOTAL DEPTH: 3918' 127.33

CONDUCTOR PIPE: 5 1/2" @ 3915'

SURFACE CASING: 8 5/8" @ 210'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR Mike's Testing & Salvage

ADDRESS: Chase KS 67524 LICENSE: 31529

COMPANY TO PLUG AT: HOUR: 9:30 DAY: 9 MONTH: April YEAR: 1996

PLUGGING PROPOSAL RECEIVED FROM Mike Kelso

COMPANY NAME: Same PHONE: _____

WERE: Sand to 3700' and 5 sacks 35 sacks - 1350' 35 sacks - 850'
260 to 0

PLUGGING PROPOSAL RECEIVED BY: Ralph Tittel

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL { } PART { } NONE { }

COMPLETED: HOUR: 1:30 DAY: 9 MONTH: April YEAR: 1996

ACTUAL PLUGGING REPORT: Sanded bottom to 3700' and 5 sacks of common. Shot 5 1/2" casing off at 2730'. Pulled to 1350'. Pumped 35 sacks. Pulled to 850'. Pumped 35 sacks. Pulled to 260'. Circulated cement to surface.

RECEIVED
KANSAS CORPORATION COMMISSION

REMARKS: 60/40 4% United #2304

I DID OBSERVE THIS PLUGGING.

JUN 06 1996

INVOICED

Jack Luthi
Jack Luthi
CONSERVATION DIVISION
WICHITA, KS
AGENT

DATE JUN 07 1996

FORM CP-2/3
REV. 3/90

INV. NO. 45751

Doc