

1 050777

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

Docket No. D-19,067
API NUMBER 15- 185-20,688

NW SW SE, SEC. 30, T 21 S, R 13 ^{WEST} _{W/E}

990 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4678

Lease Name Keenan Well # 2 SWD

Operator: LASMO Energy Corp.

County Stafford

Name & Address (Southern States)

Well Total Depth 3865 ^{125.61} feet

2700 E. 51st Street, # 480

Conductor Pipe: Size _____ feet

Tulsa, OK 74105

Surface Casing: Size 8 5/8 feet 317

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12:30 pm Day: 6 Month: March Year: 19 86

Plugging proposal received from Clay Duntz

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 3803' Open hole Tubing in two at 700'

Pump 30 sx cement, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30 pm Day: 6 Month: March Year: 19 86

ACTUAL PLUGGING REPORT Pumped 30 sx cement, 10 sx gel, 50 sx cement, 5 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 125 sx cement.

Maximum pressure 700 psi and shut in 200 psi

Remarks: Recovered 700' 5 1/2" casing. Used 60/40 Pozmix 6% gel.
(if additional description is necessary, use BACK of this form.)

I did observe this plugging.

DATE MAR 12 1986

STATE CORPORATION COMMISSION Signed Richard W. Lacey (TECHNICIAN)

MAR 11 1986

INV. NO. 12936