

15.185.20168.0000 226 R

1 010149

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5929

Operator: Duke Drilling Company, Inc.  
Name & Address: P. O. Box 823  
Great Bend, KS 67530

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 2:15 pm Day: 25 Month: June Year: 19 86

Plugging proposal received from Millard Kelso

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 3510' Perfs at 3449-3455'; 3414-18'

1st plug sand back to 3375' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, and 120 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 3:00 pm Day: 25 Month: June Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 3375' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 120 sx cement.

Maximum pressure 750 psi and shut in 100 psi

Remarks: Recovered 2800' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied  
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging RECEIVED  
STATE CORPORATION COMMISSION  
Signed

*Paul A. Luthi*  
(TECHNICIAN)

DATE JUL 10 1986

JUL - 8 1986

INV. NO. 14316

CONSERVATION DIVISION  
Wichita, Kansas

FORM CP-2/3  
Rev. 01-84