

1052358

TO: STATE CORPORATION COMMISSION

API NUMBER 15-185-10,365.0004  
SW SW NW SEC. 6, T 21 S, R 11 W

CONSERVATION DIVISION - PLUGGING SECTION 2970 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 4950 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME FISHER WELL # 2

TECHNICIAN'S PLUGGING REPORT

COUNTY STAFFORD 114.47

OPERATOR LICENSE # 5234

WELL TOTAL DEPTH 3522 FEET

OPERATOR: PENGUIN PETROLEUM, INC. PRODUCTION CSG: SIZE 5 1/2" @ 3438' WITH 75 SX

NAME AND 1200 MAIN STREET #404 SURFACE CASING: SIZE 8 5/8" @ 302' WITH 200 SX

ADDRESS HAYS, KS 67601

ABANDONED OIL WELL  GAS WELL  INPUT WELL  INJ WELL  D/A

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31529

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 06 MONTH: 12 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM MONTE

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945

WERE: PERFS AT 3405-11 3438-70 OPEN HOLE

SANDED TO 3298' AND 5 SX CEMENT WITH DUMP BAILER. PUMP DOWN 8 5/8" WITH 300# HULLS - 10 SX

GEL - 50 SX CEMENT - 10 SX GEL - 100# HULLS - 125 SX CEMENT. MAXIMUM PRESSURE AT 500#.

SHUT IN AT 250#.

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL  PART  NONE

OPERATIONS COMPLETED: HOUR: 10:15 AM DAY: 06 MONTH: 12 YEAR: 1999

ACTUAL PLUGGING REPORT \_\_\_\_\_

SANDED TO 3298' AND 5 SX CEMENT WITH DUMP BAILER. PUMP DOWN 8 5/8" WITH 300# HULLS - 10 SX

GEL - 50 SX CEMENT - 10 SX GEL - 100# HULLS - 125 SX CEMENT. MAXIMUM PRESSURE AT 500#.

SHUT IN AT 250#.

**INVOICED**

DATE 12/21/99

DEC 13 1999

12-13-99

RECEIVED  
KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
WICHITA, KS

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1518' OF 5 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Richard M. Lacey (TECHNICIAN) FORM CP-273