

1 120459

8-24

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-20,686.0000

SW NW NE, SEC. 6, T 21 S, R 11 W/E
4290 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6988

Lease Name Donnabaugh Well # 1

Operator: Smith Oil Operations

County Stafford 113.75

Name & Address P.O. Box 550

Well Total Depth 3500 feet

Hutchinson, KS 67504

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 258

Abandoned Oil Well Gas Well _____ Input Well _____ SMD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kizzar Well Servicing, Inc. License Number 7686

Address P.O. Box 346, Chase, KS 67524

Company to plug at: Hour: 9 a.m. Day: 24 Month: 8 Year: 19 90

Plugging proposal received from Jack Schleuning

(company name) Smith Oil Operations (phone) 316-663-6622

were: 4 1/2" at 3498' w/125 sx cement, Perfs at 3442-46'

1st plug sand back to 3390' and dump 4 sx cement on top of sand through bailer,
2nd plug run tubing to 810', pump 6 sx gel and 200 lbs. hulls, lay down 7 joints tubing,
and circulate cement to surface with 200 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4 p.m. Day: 24 Month: 8 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 3390' and dumped 4 sx cement on top of
sand through bailer,

2nd plug ran tubing to 810', pumped 6 sx gel and 200 lbs. hulls, layed down 7 joints of
tubing and circulated cement to surface with 200 sx cement.

Tubing stuck from 590-150'.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2500' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

RECEIVED

Signed Duane Rankin
(TECHNICIAN)

DATE: 8-30-90

INV. NO. 29186

8-24