

To: 1 120652  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056  
Operator: F.G. Holl Company  
Name & Address: P.O. Box 780167  
Wichita, KS 67207

12-5 15.185.19525.0000  
API NUMBER 15-Drill Completion Date 4/9/61  
SE SE SW, SEC. 6, T 21 S, R 11 W/EX  
330 feet from S section line  
2970 feet from E section line

Lease Name Sparks Well # 1  
County Stafford 113.42  
Well Total Depth 3490 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 279

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 8:30 a.m. Day: 5 Month: 12 Year: 19 91

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2", Open hole

1st plug sand back to 3375' and dump 4 sx cement on top of sand through bailer,

2nd plug pump in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 200 lbs. hulls and 125 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 9:30 a.m. Day: 5 Month: 12 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 3375' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 200 lbs. hulls and 125 sx cement.

Pumping pressure 0-1000 psi and shut in 400 psi.

RECEIVED  
STATE CORPORATION COMMISSION

DEC 10 1991

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. Recovered 1800' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

(old / ~~XXXXXX~~) observe this plugging.

DATE 12-11-91

Signed Duane Rankin (TECHNICIAN)

INV. NO. 34117