

To: 1 120653
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION E/2 E/2 SW, SEC. 6, T 21 S, R 11 W/EX
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

12-5 15.185-30370.0000
API NUMBER 15- 12/19/66

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Operator: F.G. Holl Company
Name &
Address P.O. Box 780167
Wichita, KS 67207

1320 feet from S section line
2970 feet from E section line

Lease Name Sparks Well # 2
County Stafford 112.06

Well Total Depth 3448 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 258

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9:30 a.m. Day: 5 Month: 12 Year: 19 91

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

work: 4 1/2" at 3426' w/175 sx cement, Open hole, 4 1/2" has been squeezed from 310' to surface

1st plug pump in 4 1/2" casing with 300 lbs. hulls and 175 sx cement,

2nd plug pump in 8 5/8" X 4 1/2" annulus with 50 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11 a.m. Day: 5 Month: 12 Year: 1991

ACTUAL PLUGGING REPORT 1st plug pumped into 4 1/2" casing with 300 lbs. hulls and 170 sx cement. Pumping pressure 0-2000 psi and shut in 2000 psi.

2nd plug pumped 1/2 bbl. cement slurry in 8 5/8" X 4 1/2" annulus and 3 sx cement.

Pumping pressure 0-800 psi and shut in 800 psi.

RECEIVED
STATE OF KANSAS
CORPORATION COMMISSION
DEC 10 1991
L. J. HAVAN
Wichita, Kansas

Remarks: Used 60/40 Pozmix 8% gel by HOWCO. No casing recovery.

(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-11-91

Signed Duane Rankin
(TECHNICIAN)

INV. NO. 34118