

1051653

S-25

API NUMBER 15-185-22,899.0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE NE SW , SEC. 6 , T. 21 S, R. 11 W/EK
1650 feet from S section line
2310 feet from W/EK section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6039

Lease Name Ochs Well # 1

Operator: L.D. Drilling, Inc.

County Stafford 112.51

Name & Address RR 1, Box 183 B

Well Total Depth 3462 feet

Great Bend, KS 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 339

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1 p.m. Day: 25 Month: 5 Year: 19 93

Plugging proposal received from Vernon Duntz

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 3448' w/145 sx cement, Open hole 3462'

1st plug sand back to 3400' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:05 p.m. Day: 25 Month: 5 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 3400' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement. Maximum pressure 500 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1800' of 5 1/2" casing.

RECEIVED

INVOICED

DATE 6-4-93

Signed Richard W. Lacey (TECHNICIAN)

JUN 4 1993

INV. NO. 37826

CONSERVATION DIVISION Wichita, Kansas

FORM CP-2/3 Rev. 01-84