

1 060483

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION W/2
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,166-0000

SW NW , SEC. 7 , T 21 S, R 11 W/X

3300 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Schlochtermietwell # 1

Operator: TXO Production Corp.

County Stafford 115.38

Name & Address 200 W. Douglas, Suite 300

Well Total Depth 3550 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 305 ✓

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor DaMac Drilling, Inc. License Number 6333

Address Box 1164, Great Bend, KS 67530

Company to plug at: Hour: 9:00 am Day: 10 Month: February Year: 19 85

Plugging proposal received from Gerald Veatch

(company name) TXO (phone) 316-265-9441

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 620' with 50 sx cement

2nd plug at 310' with 40 sx cement

solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement.

5th plug to circulate rat hole with 15 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Paul A. Luthi

(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 10:45 am Day: 10 Month: February Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 620' with 50 sx cement, 2nd plug at 310' with 40

sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface

with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement, 6th plug to

circulate mouse hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun

(If additional description is necessary, use BACK of this form.)

INVOICED

(I did not) observe this plugging.

DATE 2-25-85

Signed Paul A. Luthi (TECHNICIAN)

INV. NO. 7100

2-10