

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-19009-00-00
Spot: NESENE Sec/Twnshp/Rge: 7-21S-11W
1650 feet from N Section Line, 330 feet from E Section Line
Lease/Unit Name: SCHLOCHTERMEIER Well Number: 4
County: STAFFORD Total Vertical Depth: 3495 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

Conductor Pipe: Size feet: 8 1/3.59
Surface Casing: Size 8.625 feet: 276
Production: Size 4.5 feet: 3435 WITH 100 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 05/16/2002 1:30 PM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3300' WITH 4 SX CMT ON TOP. 1ST PLUG AT 600' WITH 50 SX CMT. 2ND PLUG AT 300' WITH 30 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. USE 10 SX GEL FOR SPACER.

Plugging Proposal Received By: STEVE MIDDLETON

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 05/16/2002 2:45 PM

KCC Agent: RICHARD LACEY

Actual Plugging Report:

PERFS AT 3401-05, 3432-35, 3440-44, & 3451-55'. SANDED TO 3345' & 4 SX CMT WITH DUMP BAILER. 1ST PLUG AT 600' WITH 10 SX GEL - 100# HULLS - 50 SX CMT. 2ND PLUG AT 300' WITH 100# HULLS - 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

RECEIVED

MAY 29 2002

KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1800' OF 4 1/2" CASING.

Plugged through: TBG

District: 01

Signed Richard M. Lacey
(TECHNICIAN)

INVOICED MAY 24 2002
DATE 5-30-02
INV. NO. 2002061857 MP

Form CP-212