

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-13186-00-00
Spot: W2SENE Sec/Twnshp/Rge: 7-21S-11W
4290 feet from S Section Line, 400 feet from E Section Line
Lease/Unit Name: SCHLOCHTERMEIER Well Number: 3
County: STAFFORD Total Vertical Depth: 3535 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

Conductor Pipe: Size feet: 8 1/4 .89
Surface Casing: Size 8.625 feet: 254
Production: Size 5.5 feet: 3495 WITH 150 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 05/14/2002 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3340' & 5 SX CMT. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 285' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 05/14/2002 11:15 AM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

PERFS AT 3397-3401, 3429-33, 3449-55, 3448-50, 3456-61'. CIBP @ 3468'. SAND BACK TO 3340' WITH 5 SX CMT ON TOP. 1ST PLUG RUN 2 3/8" TUBING TO 620'. PUMP 10 SX GEL & 50 SX CMT. 2ND PLUG PULL TO 280' & PUMP 50 SX CMT. 3RD PLUG PULL TO 0-40' & PUMP 10 SX CMT. GOOD CIRCULATION THROUGHOUT JOB.

RECEIVED
MAY 17 2002
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2020' OF 5 1/2" CASING.

Plugged through: TBG

District: 01

Signed _____

(TECHNICIAN)

INVOICED
DATE 5-20-02
INV. NO. 2002061791

MAY 15 2002

FORM CP 213