

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-21,275.0000

SW NE SW, Sec. 30, T 21 S, R 11 W/E

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5230

Lease Name Duggan Well # 1

Operator: Petroleum Energy, Inc.
Name & Suite 415, First Nat'l Bank Bldg.
Address 105 N. Main St.
Wichita, KS 67202

County Stafford

Well Total Depth 3530 feet 114.72

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 251

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 1:00 pm Day: 13 Month: February Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO James Ray

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: PBTD 3510 Perfs 3492 - 98 4 1/2 set at 3520

1st plug sanded back to 3540 and dumped 4 sx cement on top of sand

2nd plug squeezed through head with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx

gel 1 sack hulls and released 8 5/8" rubber plug and pumped 125 sx cement.

Maximum pressure 300# and shut-in pressure 100#

Signed Steve Quaint
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 4:00 pm Day: 13 Month: February Year: 19 84

ACTUAL PLUGGING REPORT PBTD 3510 Perfs 3492 - 98 4 1/2 set at 3520'

1st plug sanded back to 3540' and dumped 4 sx cement on top of sand

2nd plug squeezed through head with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx

gel, 1 sack hulls and released 8 5/8" rubber plug and pumped 125 sx cement.

Maximum pressure 300# and shut-in pressure 100#.

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Allied. They recovered 2900' 4 1/2" production casing.

RECEIVED
STATE CORPORATION COMMISSION
FEB 15 1984
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as hereon stated and that I (did / ~~did not~~) observe this plugging.

Signed Steve Quaint
(TECHNICIAN)

INVOICED
DATE 2-22-84
INV. NO. 0298