

To: 1 120835 9-30
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,343.0000
SE NW SW, SEC. 30, T 21 S, R 11 W/E
1650 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6039
Operator: L.D. Drilling, Inc.
Name: RR 1, Box 183 B
Address: Great Bend, KS 67530

Lease Name Duggan Well # 1
County Stafford 118.20
Well Total Depth 3640 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 300

Abandoned Oil Well Gas Well _____ Input Well _____ SMD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1 p.m. Day: 30 Month: 9 Year: 19 93

Plugging proposal received from Mike Kelso
(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 5 1/2" at 3636' w/150 sx cement, Perfs at 3523-3576' (6 sets)
1st plug sand back to 3470' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 125 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 p.m. Day: 30 Month: 9 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 3470' and dumped 5 sx cement on top of sand
through bailer,

2nd plug pumped into 8 5/8" surface casing with 250 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 150 lbs. hulls and 125 sx cement.

Pumping pressure 0-600 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2237' of 5 1/2" casing.

INVOICED (If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

DATE 10-7-93

INV. NO. 38901

Signed Duane Rankin
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
OCT 06 1993
CONSERVATION DIVISION
Wichita, Kansas