

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-073-20013-00-00  
Spot: SENESESW Sec/Twnshp/Rge: 12-24S-12E  
708 feet from S Section Line, 2820 feet from E Section Line  
Lease Name: DAME Well #: 8  
County: GREENWOOD Total Vertical Depth: 1738 feet

Operator License No.: 33861  
Op Name: ALLEN'S SERVICE INC. DBA RUDE CR  
Address: PO BOX 145  
HAMILTON, KS 66853

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	1701		0 SX
SURF	16	16		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/22/2017 9:00 AM  
Plug Co. License No.: 99973 Plug Co. Name: ELITE CEMENTING AND ACID SERVICE, LLC  
Proposal Rcvd. from: ALLEN DANNELS Company: \_\_\_\_\_ Phone: (620) 678-3836

Proposed Plugging Method: Set bridge plug in bottom, cement with 20 sacks. Perforate 2 holes at 700 ft., cement with 20 sacks. Perforate 2 holes at 225 ft., cement to surface inside and out. Set jell bridges between cement.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: NONE  
Date/Time Plugging Completed: 09/22/2017 1:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report: \_\_\_\_\_ Perfs: \_\_\_\_\_

Ran tubing to 1665', pumped 20 sxs cement, pulled tubing to 700', pumped 20 sxs cement, pulled tubing to 225', pumped 40 sxs cement to surface, gel spacers between cement plugs, casing shot @ 700' & 225'.

RECEIVED  
KCC DIST # 3  
SEP 25 2017  
CHANUTE, KS  
*MH*  
INVOICED  
SEP 26 2017

Remarks:  
Plugged through: TBG

District: 03 Signed Mik Miller  
(TECHNICIAN)

810 E 7<sup>TH</sup>  
 PO Box 92  
 EUREKA, KS 67045  
 (620) 583-5561



15-073-20013  
 Cement or Acid Field Report  
 Ticket No. **3543**  
 Foreman Russell McCoy  
 Camp EUREKA

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
9-22-17	1,043	DAME # 8	12	24	12	G.W.	KS
Customer <u>RUDE CLUDE</u>			Unit #	Driver	Unit #	Driver	
Mailing Address <u>BOX 145</u>			102	RICK			
City <u>HAMILTON</u>			112	AB			
State <u>KS</u>			145	STEVE			
Zip Code <u>66853</u>							

Job Type \_\_\_\_\_ Hole Depth \_\_\_\_\_ Slurry Vol. \_\_\_\_\_ Tubing 2 3/8  
 Casing Depth \_\_\_\_\_ Hole Size U.V. KNOWN Slurry Wt. \_\_\_\_\_ Drill Pipe \_\_\_\_\_  
 Casing Size & Wt. 7" Cement Left in Casing \_\_\_\_\_ Water Gal/SK \_\_\_\_\_ Other \_\_\_\_\_  
 Displacement \_\_\_\_\_ Displacement PSI \_\_\_\_\_ Bump Plug to \_\_\_\_\_ BPM 4

Remarks: Safety meeting SPOT 20 SKS 1665'  
 SPOT 20 SKS 700'  
 SPOT 40 SKS 225 TO SURFACE  
 MC SKS TOTAL

Gel SPACER Between Plugs  
BUILD BRIDGE @ 230' w/ R.G.

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C-105a	1	Pump Charge	500.00	500.00
C-107	15	Mileage	3.95	59.25
C-203	80	SKS 6440 P-2 mix	12.75	1020.00
C-108		Tax Mileage	1/2 m/c	172.50
C-113	1	hr 80 Bbl VAC TRUCK	85.00	85.00
				1836.75
		Sales Tax		137.16
Authorization	<u>by ALLEN DANE</u>		Title	<u>OWNER</u>
		Total		<u>1973.91</u>

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.