

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-063-22099-00-00
Spot: NESWSENW Sec/Twnshp/Rge: 18-11S-26W
2219 feet from N Section Line, 1761 feet from W Section Line
Lease Name: BROOKS Well #: 1-18
County: GOVE Total Vertical Depth: 4572 feet

Operator License No.: 34579
Op Name: COBALT ENERGY LLC
Address: 115 S. BELMONT #12 PO BOX 8037
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4553		200 SX
SURF	8.625	269		190 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/24/2017 8:30 AM
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.
Proposal Rcvd. from: DIRK PARKS Company: COBALT ENERGY LLC Phone: (785) 216-0039

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/700 # hulls. Perforations at 4084' - 4091' and 4414' - 4420'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/24/2017 12:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 4300' and pumped 100 sx cement w/350 # hulls. Pulled tubing to 3000' and pumped 100 sx cement w/50 # hulls. Pulled tubing to 1500' and pumped 100 sx cement. Good circulation of cement. Pulled tubing out. Topped off casing with 10 sx cement. Tied on to backside and squeezed with 10 sx cement. Shut in pressure 200 psi.

GPS: 39.09768 -100.25284

Perfs:

Top	Bot	Thru	Comments
4414	4420		
4084	4091		

Remarks: QUALITY CEMENT TICKET # 1896

Plugged through: TBG

INVOICED
SEP 26 2017

District: 04

Signed _____

Marvin Mills
(TECHNICIAN)

CM

KCC WICHITA

SEP 14 2017

RECEIVED

AUG 25 2017