

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-191-20889-00-01
Spot: NENE Sec/Twnshp/Rge: 8-35S-2E
4620 feet from S Section Line, 660 feet from E Section Line
Lease Name: MESSENGER Well #: 2-8
County: SUMNER Total Vertical Depth: 944 feet

Operator License No.: 5558
Op Name: DAWSON-MARKWELL EXPLORATION
Address: 1249 EAST 33RD
EDMOND, OK 73013

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	944		120 SX
SURF	8.625	180		55 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/11/2017 10:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: TRIPP MARKWELL Company: DAWSON MARKWELL EXPLORAT Phone: (405) 232-0418

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX WitnessType: PARTIAL
Date/Time Plugging Completed: 04/11/2017 11:00 AM KCC Agent: DAN FOX

Actual Plugging Report:

ON 2/28/17 A CIBP WAS SET @ 770' CAPPED WITH 2 SX OF CEMENT. ON 4/11/17 PLUGGING CONTRACTOR RAN IN WITH POLY TO 320' AND CIRC. CEMENT TO SURFACE. PULLED OUT POLY AND RAN THE 1" DOWN THE BACKSIDE OF 4.5" TO 25' COULD NOT GET POLY DOWN NO FURTHER. CIRCULATE CEMENT TO SURFACE FROM THERE. LET ET AND CASING STOOD FULL. 40 SX TOTAL OF CEMENT. CAME BACK NEXT DAY TO CHECK TOP PLUG AND NO FURTHER MOVEMENT IN PLUG. JOB COMPLETE. GRESSEL CEMENT TICKET NUMBER 44925.

Perfs:

Top	Bot	Thru	Comments
834	838	TBG	
813	828		


INVOICED
SEP 26 2017

Remarks: DENIED TA

Plugged through: TBG

District: 02

Signed


(TECHNICIAN)

JK