

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-051-02694-00-00  
Spot: SESWNE Sec/Twnshp/Rge: 7-13S-17W  
2970 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: STAAB C Well #: 3  
County: ELLIS Total Vertical Depth: 3628 feet

Operator License No.: 5145  
Op Name: DREILING OIL INC  
Address: 1008 CODY AVE PO BOX 550  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3627		125 SX
SURF	8.625	921		400 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/28/2017 7:30 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: AVEN WEAVERLING Company: DREILING OIL INC Phone: (785) 623-3221

Proposed Plugging Method: Ordered 600 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
Casing leaks: 77 joints on tubing 1928'.  
Fluid level 850'.  
Cleaned out 40' DelgrMud.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/28/2017 12:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Gemini Logging perforated at 1700', 1250' and 900'. Express Well Service ran in hole with tubing to 3503' and pumped 115 sx cement w/300 # hulls mixed in. Pulled tubing to 2357' and pumped 150 sx cement w/100 # hulls mixed in. Pulled tubing to 960' and pumped 100 sx cement w/100 # hulls to circulate 5 1/2" casing. No circulation on 8 5/8" casing. Pulled tubing. Rigged to 5 1/2' casing with a swedge and pumped 10 sx cement to pressure with 300 psi. Shut in pressure 300 psi. Rigged to 8 5/8" casing and pumped 2 sx cement w/300 psi. Shut in pressure 300 psi.

GPS: 38.93717 -099.24879


Perfs:

Remarks: QUALITY OILFIELD CEMENTING TICKET # 1896

Plugged through: TBG

District: 04

Signed \_\_\_\_\_



(TECHNICIAN)

CM

KCC WICHITA

SEP 14 2017

RECEIVED

AUG 29 2017

Form CP-2/3

INVOICED  
SEP 26 2017