

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-02900-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 16-9S-21W
2970 feet from S Section Line, 2310 feet from E Section Line
Lease Name: BOLAND Well #: 5
County: GRAHAM Total Vertical Depth: 3677 feet

Operator License No.: 34916
Op Name: FOURWINDS OIL CORPORATION
Address: PO BOX 1063
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	4.5	3537		25 sx no circulation
PROD	5.5	3676		125 SX
SURF	8.625	147		125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/02/2017 12:30 PM
Plug Co. License No.: 34706 Plug Co. Name: GASCHLER PULLING SERVICE, INC.
Proposal Rcvd. from: DAN WINDHOLZ Company: FOURWINDS OIL CORPORATION Phone: (785) 259-8403

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Well had been squeezed at 2015' w/200 sx cement and 1880' w/200 sx cement.
Open hole: 3675' - 3676'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/23/2017 10:00 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Shot perforations 2 holes at 975'. Ran tubing to 3598' and pumped 75 sx cement w/250 # hulls. Pulled tubing to 2587' and pumped 75 sx cement. Pulled tubing to 1603' and pumped 130 sx cement. Good circulation of cement. Pulled tubing out and topped off casing with 25 sx cement.
08/23/2017 - Tied on to backside and squeezed with 100 sx cement. Shut in pressure 150 psi.
GPS: 39.27167 -099.66893

Perfs:


INVOICED
SEP 27 2017

Remarks: QUALITY CEMENT TICKET # 279 AND 369

Plugged through: TBG

District: 04

Signed


(TECHNICIAN)

CM

KCC WICHITA

AUG 25 2017

SEP 14 2017

RECEIVED