

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-083-21784-01-00
Spot: N2N2NENE Sec/Twnshp/Rge: 31-23S-22W
5095 feet from S Section Line, 671 feet from E Section Line
Lease Name: IMEL Well #: 1-31H
County: HODGEMAN Total Vertical Depth: 4705 feet

Operator License No.: 32970
Op Name: H-D OILFIELD SERVICE, INC.
Address: PO BOX 87
BAZINE, KS 67516

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4671		
COND	20	100		WITH 266 SX CMT
PROD	7	5239	846	WITH 525 SX CMT
SURF	9.625	815		WITH 350 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/05/2017 11:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JEFF WERTH Company: H-D OILFIELD SERVICES Phone: (785) 798-7677

Proposed Plugging Method: CIBP ALREADY SET AT 4671'. PLUG AT 1530' WITH 15 SX GEL & 50 SX CMT. PLUG AT 840' WITH 75 SX CMT. PLUG AT 400' WITH 40 SX CMT. PLUG AT 60' WITH 30 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/06/2017 2:45 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

CIBP ALREADY SET AT 4671'. TRIED SHOOTING THE CASING OFF AT 1500' BUT COULD NOT PULL FREE. TRIED PUMPING INTO IT BUT PRESSURED TO 2000#. PERFORATED AT 1500'. ESTABLISHED A RATE OF 1 1/2 BPM AT 1200#. 1ST PLUG AT 1500' WITH 50 SX CMT. WHILE DISPLACING, RATE CHANGED TO 3 BPM AT 1000#. SHOT CASING OFF AT 846'. 2ND PLUG AT 846' WITH 75 SX CMT. 3RD PLUG AT 402' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 35 SX CMT. CMT CIRCULATED & THE HOLE STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
5365			

INVOICED
SEP 27 2017

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES. TMD=9193'

Plugged through: CSG

District: 01

Signed _____

RECEIVED
SEP - 8 2017
KCC DODGE CITY

(TECHNICIAN)