

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-073-21768-00-01  
Spot: NESWNE Sec/Twnshp/Rge: 27-25S-8E  
1618 feet from N Section Line, 1587 feet from E Section Line  
Lease Name: HAWTHORNE Well #: 14  
County: GREENWOOD Total Vertical Depth: 2628 feet

Operator License No.: 5697  
Op Name: JACKSON BROTHERS, L.L.C.  
Address: 116 E 3RD ST  
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2564		
PROD	4.5	2618		50 SX
SURF	8.625	100		50 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/07/2017 12:00 AM  
Plug Co. License No.: 6112 Plug Co. Name: LONG DRILLING COMPANY, LLC  
Proposal Rcvd. from: ROSCOE G. JACKSON II Company: \_\_\_\_\_ Phone: (620) 583-5122

Proposed Plugging Method: 1. 50-foot plug inside 4.500" casing at 2564-2514' K.B.2. 50-foot plug inside 4.500" casing at 2480-2430' K.B.3. Continuous cement plug inside and outside 4.500" at 1240-1190' K.B.4. Continuous cement plug inside and outside 4.500" from 250 ft. to land surface.

Plugging Proposal Received By: MICHAEL HEFFERN Witness Type: PARTIAL  
Date/Time Plugging Completed: 09/12/2017 1:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran dump baler to 2564' on rock bridge, spotted 7 sxs cement, ran tubing to 1240' on rock bridge pumped 20 sxs cement, pulled tubing out built rock bridge @ 250', pumped 85 sxs cement to surface,

Perfs:

Top	Bot	Thru	Comments
2609	2616		
2498	2504		

RECEIVED  
KCC DIST # 3  
SEP 18 2017  
CHANUTE, KS

*MH*

INVOICED  
SEP 27 2017

Remarks:

Plugged through: TBG

District: 03

Signed *Michael Heffern*  
(TECHNICIAN)

Received 12 Sept 2017

810 E 7<sup>th</sup>  
 PO Box 92  
 EUREKA, KS 67045  
 (620) 583-5561



Cement or Acid Field Report  
 Ticket No. **3521**  
 Foreman Steve Reed  
 Camp Eureka KS

Date	Cust ID #	Lease & Well Number	Section	Township	Range	County	State
9-12-17	1008	Hawthorne #141	27	25S	8E	Greenwood	KS
Customer Jackson Brothers LLC			Unit #		Driver	Unit #	Driver
Mailing Address 116 E Third			102		Rick		
City Eureka			110		Jason		
State KS			141		Alan		
Zip Code 67045							

Job Type PTA oilwell Hole Depth \_\_\_\_\_ Slurry Vol \_\_\_\_\_ Tubing \_\_\_\_\_  
 Casing Depth \_\_\_\_\_ Hole Size 6 3/4 Slurry Wt. \_\_\_\_\_ Drill Pipe \_\_\_\_\_  
 Casing Size & Wt. 4 1/2 Cement Left in Casing \_\_\_\_\_ Water Gal/SK \_\_\_\_\_ Other \_\_\_\_\_  
 Displacement \_\_\_\_\_ Displacement PSI \_\_\_\_\_ Bump Plug to \_\_\_\_\_ BPM \_\_\_\_\_

Remarks: Safety Meeting Spot Rocks AT 1240'  
Spot 6.5 SKS 250' to surface  
Total 8.5 SKS 6y/40 Por mix 4% Gel

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C105	1	Pump Charge	750.00	750.00
C107	15	Mileage	3.95	59.25
C203	85.5ks	60/40 Pozmix Cement	12.75	1083.75
C206	290 <sup>+</sup>	Gel 4%	.20	58.00
C108A	3.66 Ton	Formaldehyde Bulk Truck	171.00	345.00
C113	3 hrs	80 bbl. UAC Truck	85.00	255.00
		<u>Total 2742.33</u>		
		<u>-5% Discount 137.12</u>		
		<u>Total 2605.21 OK</u>		
			Sub Total	2551.00
			Sales Tax 7.5%	191.33
Authorization <u>Roscoe L Jackson II</u> Title <u>CO-MANAGER</u>			Total	2742.33

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.

# Well Master Data

[Search T-1's / Letters](#)

[Search Well Inventory](#)

[Get Cnty From Legal](#)



API Well #	15	073	21768	00	01	Create Next API for This Well	Well Doc Images	Well History
District Dkt #								
Lse Nm	HAWTHORNE				Well No	14		
Oper/Status	5697	Find	Jackson Brothers, L.L.C.				A	
Work Oper:								
Source:			Effec Dt:			Request T-1		
Lgcy Oper	JACKSON BROTHERS							
C-1 Oper								
Driller/Status								
Lgcy Drllr	LONG DRILG CO							

Status	AX
Stat Source	CPI
Type	OIL
C-1 Well Type	
Type Cmpl	
Dkt / Permit	
District	03
KDOR Lease Code:	
Oil	Gas
102280	

DATES FOR THIS API #	
Status Dt	09/06/2017
Intent Dt	
Intent Exp	
ACO-1 Spud	09/17/1992
Dist Spud	#####
LngStrng	
TD Rchd	
CmpltD Dt	09/23/1992
1st Prod	
1st Inj	
PB TD Dt	
P/A Dt	

Lease Inspection Date

### Master Well File Comments

Date/By	Well Comment
09/07/2017 bdyke	Plugging started 9/7/17 Tom Long 437-7444-
09/01/2006 RBDMSadm	Well Status changed FROM: TA (Temporarily Abandoned) TO: IN (Inactive Well) effective 09/01/2006 per changes to well status codes and definitions.
05/03/2005 RBDMSadm	RPFPB -- historical information added 05/03/05 from original data source DEFNRECPD.

<Shif(+<F2> will expand comment fields!

Const	TVD
Kickoff	
Plug Back	2564
Hole	2628
Loggers	2628
Last Edited:	09/06/17
By:	rherterm

WI Loc 27-25S-8E NESWNE, 1618 FNL 1587 FEL TA Stat

State Add. Prod-Geo Strings Perfs Stim Logs Pluggings UIC TA EPR