

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-20454-00-00
Spot: SWSENE Sec/Twnshp/Rge: 12-17S-13W
2970 feet from S Section Line, 990 feet from E Section Line
Lease Name: OGLE (LINSNER) Well #: 2-D
County: BARTON Total Vertical Depth: 3399 feet

Operator License No.: 3208
Op Name: K & N PETROLEUM, INC.
Address: 1105 WALNUT
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3396		125 SX
SURF	8.625	281		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/14/2017 2:00 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: ED NEMNICH Company: K & N PETROLEUM, INC. Phone: (620) 793-5838

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement, 13 sx gel and 500 # hulls.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/15/2017 11:00 AM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1400', 830' and 275'.
08/14/2017 - Ran tubing to 3250' and pumped 13 sx gel followed by 50 sx cement w/200 # hulls. Pulled tubing.
08/15/2017 - Perforated at 1400', 830' and 275'. Ran tubing to 1405' and pumped 60 sx cement w/200 # hulls. Pulled tubing to 850' and pumped 60 sx cement. Pulled tubing to 300'.
Circulated cement to surface on casing. Pulled tubing. Tied to casing and circulated cement to surface on surface pipe with 25 sx cement.

GPS: 38.58796 -098.70514

Perfs:

Top	Bot	Thru	Comments
3396	3399		
3217	3222		
2992	3002		
2960	2970		
2852	2862		

Remarks: COPELAND ACID AND CEMENT

Plugged through: CSG

INVOICED
SEP 27 2017

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

CM

KCC WICHITA

WUG 22 2017

SEP 14 2017

Form CP-2/3

RECEIVED