

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-26141-00-00  
Spot: SWSWNWSW Sec/Twnshp/Rge: 14-18S-14W  
1585 feet from S Section Line, 130 feet from W Section Line  
Lease Name: SKOLAUT-MAULER UNIT Well #: 1-14  
County: BARTON Total Vertical Depth: 3520 feet

Operator License No.: 6039  
Op Name: L. D. DRILLING, INC.  
Address: 7 SW 26TH AVE  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3511	2370	180 SX
SURF	8.625	855		400 SX
T1	2.875	3465		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/07/2017 12:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KASSELMAN Company: L. D. DRILLING, INC. DBA Phone: (620) 793-3051

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/13/2017 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Cut casing at 1823'. Pulled casing to 1450' and pumped 125 sx cement w/200 # hulls. Pulled casing to 900' and pumped 60 sx cement w/100 # hulls. Pulled casing to 600' and pumped 50 sx cement w/100 # hulls. Pulled casing to 300'. Circulated cement to surface with 75 sx cement. Pulled casing and hole stayed full.

GPS: 38.48204 -098.84816

Perfs:

Top	Bot	Thru	Comments
3417	3419		

Remarks: BASIC CEMENTING

Plugged through: CSG

INVOICED  
SEP 27 2017

District: 04

Signed Bruce Rodie  
(TECHNICIAN) CM

KCC WICHITA

SEP 14 2017

RECEIVED

AUG 18 2017