

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-26044-00-00
Spot: SENWSENW Sec/Twnshp/Rge: 21-18S-14W
1882 feet from N Section Line, 1864 feet from W Section Line
Lease Name: BARNES Well #: 1-21
County: BARTON Total Vertical Depth: 3535 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3530	2500	180 SX
SURF	8.625	914		400 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/09/2017 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KASSELMAN Company: L. D. DRILLING, INC. DBA Phone: (620) 793-3051

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/11/2017 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Cut casing at 2500'. Pulled casing to 1450' and pumped 125 sx cement w/200 # hulls. Pulled casing to 900' and pumped 60 sx cement w/100 # hulls. Pulled casing to 600' and pumped 50 sx cement w/100 # hulls. Pulled casing to 300'. Circulated cement to surface with 75 sx cement. Pulled casing and hole stayed full.

GPS: 38.47271 -098.87897

Perfs:

Top	Bot	Thru	Comments
3388	3392		

Remarks: BASIC CEMENTING

Plugged through: CSG

INVOICED
SEP 27 2017

District: 04

Signed

Bruce Rodie
(TECHNICIAN)

CM

KCC WICHITA

SEP 14 2017

RECEIVED

AUG 18 2017