

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-24669-00-00
Spot: W2SWNWSE Sec/Twnshp/Rge: 14-17S-21W
1650 feet from S Section Line, 2530 feet from E Section Line
Lease Name: HIGGINS-KEADY Well #: 1
County: NESS Total Vertical Depth: 4200 feet

Operator License No.: 31528
Op Name: MIKE KELSO OIL, INC.
Address: PO BOX 467
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4130		
PROD	4.5	4199	0	WITH 385 SX CMT
SURF	8.625	221		WITH 160 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/05/2017 10:00 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: MICHAEL MAIER

WitnessType: NONE

Date/Time Plugging Completed: 09/05/2017 12:00 PM

KCC Agent: MICHAEL MAIER

Actual Plugging Report:

CIBP @ 4130'. TRIED TO REWORK WELL. COULD NOT GET BELOW 1220'. WENT OUTSIDE OF CASING WITH BIT. WORKED ON FOR 1 DAY. RUN TBG TO 1200' & PUMPED 230 SX CMT WITH 400# HULLS. PULLED TBG & TOPPED OFF WITH 120 SX CMT. PUMP 30 SX CMT ON BACKSIDE 300# PRESSURE.

Perfs:

Top	Bot	Thru	Comments
4138	4158		
4100	4102		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND

Plugged through: TBG

INVOICED
SEP 27 2017

District: 01

Signed

Michael Maier

(TECHNICIAN)

RECEIVED
SEP - 7 2017
KCC DODGE CITY

MR

JA