

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-129-20626-00-00
Spot: SWNWSW Sec/Twship/Rge: 34-34S-43W
1650 feet from S Section Line, 330 feet from W Section Line
Lease Name: LENCUT Well #: 7
County: MORTON Total Vertical Depth: 1266 feet

Operator License No.: 33373

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1265	0	WITH 350 SX CMT
SURF	8.625	417		WITH 275 SX CMT

Op Name: NAIRN, ROBERT

Address: 1120 MUNCY AVE
ELKHART, KS 67950

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 08/24/2017 9:00 AM

Plug Co. License No.: 32833

Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.

Proposal Revd. from: MARLIN CLARK

Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed
Plugging
Method:

PUMP 25 SX CMT & 150# HULLS AT 1265'. PUMP CMT FROM 440' TO SURFACE. USE 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER

WitnessType: NONE

Date/Time Plugging Completed: 08/24/2017 3:00 PM

KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PUMP 25 SX CMT AT 1266'. TAG TOC @ 915'. RAN CBL FROM 550' TO 0'. NO CMT FROM 107' TO 0'. PUMP 40 SX CMT FROM 520' TO 0'. PUMP 23 SX CMT DOWN ANNULUS.

Perfs:

Top	Bot	Thru	Comments
1265	1266	OH	

Remarks: USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: TBG

District: 01

Signed

Michael Maier

(TECHNICIAN)

RECEIVED

SEP - 7 2017

KCC DODGE CITY

518

INVOICED

SEP 27 2017