

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-23324-00-00
Spot: S2SENE Sec/Twnshp/Rge: 19-22S-10E
2310 feet from N Section Line, 660 feet from E Section Line
Lease Name: BROWNING Well #: 09
County: GREENWOOD Total Vertical Depth: 2406 feet

Operator License No.: 34479
Op Name: PATTERSON OPERATIONS LLC
Address: 618 N. WESTCHESTER DR.
ANDOVER, KS 67002

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2406		150 SX
SURF	8.625	205		100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/25/2017 1:00 PM
Plug Co. License No.: 99973 Plug Co. Name: ELITE CEMENTING AND ACID SERVICE, LLC
Proposal Revd. from: GARR PATTERSON Company: _____ Phone: (316) 651-6104

Proposed Plugging Method: According to Kansas Corporation requirements.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: NONE
Date/Time Plugging Completed: 09/25/2017 4:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Ran tubing to 2181', pumped 25 sxs cement, pulled tubing to 908', pumped 15 sxs cement, pulled tubing to 250', pumped 105 sxs cement to surface, gel spacers between cement plugs, casing shot @ 250' & 900',

Perfs:

RECEIVED
KCC DIST # 3
SEP 26 2017
CHANUTE, KS

MH

INVOICED
SEP 27 2017

Remarks:

Plugged through: TBG

District: 03

Signed

Michael Heffern
(TECHNICIAN)

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
 Ticket No. **3523**
 Foreman Steve Mead
 Camp Eureka, KS

API 15-073-23324

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
9-25-17	1044	Browning #9	19	R2	10E	Greenwood	KS
Customer			Unit #	Driver	Unit #	Driver	
Paterson Operation			102	Bick			
Mailing Address			112	TASON			
618 Westchester Dr			141	DAVE			
City		State	Zip Code				
Andover		KS	67000				

Job Type PZA old well Hole Depth _____ Slurry Vol. _____ Tubing _____
 Casing Depth 2398' Hole Size _____ Slurry Wt. _____ Drill Pipe _____
 Casing Size & Wt. 4 1/2 Cement Left in Casing _____ Water Gal/SK _____ Other Part 2280-2284'
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: SAFETY MEETING: Plug well As Follows:

Spot 25 SKS AT 2181'
Spot 15 SKS AT 908'
105 SKS - 250 To Surface
Total 145 SKS 60/40 Perm mix Cement w/ 4% Gel

Thank you

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C105.2	1	Pump Charge	500.00	500.00
C107	-	Mileage	-	-
C203	145	60/40 Perm mix Cement	12.75	1848.75
C206	500*	4% Gel	.20	100.00
C205	50*	2% Caclz	.60	30.00
C214	20*	Hulls	.45	9.00
C108A	6.24 Ton	Ton Mileage Bulk Truck	MISC	345.00
C113	3 hr	80 bbl Vac Truck	85.00	255.00
C206	200*	Gel Spacer	.20	40.00
		<u>Total</u>	<u>3362.33</u>	
		<u>Discount -5%</u>	<u>168.12</u>	
		<u>3194.21</u>		
			<u>Sub Total</u>	<u>3127.75</u>
			<u>Sales Tax</u>	<u>234.58</u>
Authorization _____ Title _____			Total	<u>3362.33</u>

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.