

15.185.0004T.0000

8

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 109-2

LOCATION NE-NE-NW

SEC. 15 TWP 21 RGE. 14

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Taylor

Operator Standard Oil & Gas Co. Address Box 7, Ellinwood Kans.

Field _____ County Stafford

Total Depth 3741 Feet.

Plugging Contractor R & S Pipe Pulling Co.

Plugging Contractor's License No. 1

Address Ellinwood, Kansas

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 7/8" @ 855' C.W.C. 5 1/2" casing set
3708' w/ 100 st cem. Top prof 3682'. Landed
hole to 3675' dumped 5 st cem. Shot off
and pulled 5 1/2" casing. Filled hole with
heavy mud to 300' set rock bridge and
dumped 20 st cem. mud to 35' rock bridge
and 10 st cem. to base of cellar

Warren H. Harner
District Conservation Agent

Date May 17, 1955

RECEIVED
STATE CORPORATION COMMISSION
MAY 19 1955
CONSERVATION DIVISION
Wichita, Kansas
5-19-1955

PLUGGING
FILE SEC 15 TWP 21 RGE 14
BOOK PAGE 109 LINE 2